Item Code	Description	Unit	Approved Quantity	Approved Rate in Figures (in Rs.)	Rate in Words (in Rupees)
151	KSRB 6-2.3 : Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 50 (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2 (P W D BCSR 2014-15, P-27, I-6.6)	cum	5.57	6563.00	Rupees six thousand five hundred and sixty three only
152	KSRB 15.3.4:Providing 15mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. (P W D BCSR. 2014-15, P-109, I-15.9)	Sqm	118.66	182.00	Rupees one hundred and eighty two only
153	KSRB 14.7-1: Providing and laying flooring with M15 cement concrete 40 mm thick using broken granite 20mm and down size laid to line and level in one layer and finish with a floating coat of neat cement , including cost of materials, labour, curing, complete as per specifications. Specification No. KBS 14.3 (P W D BCSR. 2014-15, P-98, I-14.8)	sqm	40.00	335.00	Rupees three hundred and thirty five only
154	KSRB 15.12.1Providing Gopi colour washing to new wall surface in two coats with lime and gopi colour of approved quality, to give an even shade after thoroughly brooming the surface to remove all dirt, dust, mortar drops and other foreign matter including cost of materials, labour, complete as per specifications. (P W D BCSR. 2014-15, P-112, I-15.44)	sqm	61.92	10.00	Rupees ten only
155	KSRB 7.9 : Providing and fixing M.S.grill work for windows and ventilators using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications. Specification No. KBS 7.12 (P W D BCSR. 2014-15, P-32, I-7.9)	kgs	2052.45	104.00	Rupees one hundred and four only

Contractor

Executive Engineer-2
Lakes, BBMP

Scanned by CamScanner

Item Code	Description	Unit	Approved Quantity	Approved Rate in Figures (in Rs.)	Rate in Words (in Rupees)
161	Fabrication, Supplying, Erection,Testing and Commissioning of 16 mtrs long polygon hihg mast with Single / Multiple of bottom dia 410mm and top dia 150mm with two telescopic sections having bottom piece 6.50mtrs with 3mm thick and top piece 6.50mtrs 3mm thick as per BSEN 10025 grade S 355 JO steel sheet plate for shaft suitable to withstand a wind velocity of 180kmph as per IS 875 part 3 (as per GA Drawing). Base plate having size 520mm dia, 16mm thick with 6nos. of foundation bolts M24 X 850mm long and connected accessories as per IS ISO 1461 with an average 70 microns as per IS 2629, and welded as per BS 5135 single L - seam joint. The mast, shall have two way head frame with 4nos of 190mm die cast LM -6 pulleys, steel axils, phosphorus bronze bearing bush press fitted with seperate guides for 2 runs of 5mm dia stainless steel wire rope and 5 core 2.5Sqmm EPR insulated PCP sheathed trialling power cable all are housed inside the bottoms of mast with suitable locking 250 x 950mm hinged door. The mast shall have power tool having 0.5HP, 415 V, 50Hz, 3-Phases reversible 960RPM geared motor mast. The mast shall have land turn of 2 segments,	Each	1.00	169600.00	Rupees one lakh sixty nine thousand six hundred only
162	Supplying High pressure 400 Watts Metal halide flood light luminary suitable for use with high pressure metal halide lamp with integrated control gear. The fitting shall be non-corrosive high pressure die cast aluminium housing powder coated with toughened and heat resistant glass with low copper content black/grey powder coated paint finish with EPDM gasket. Reflector shall be made of high purity pre-anodized aluminium. Cable entry through a cable gland with toggle clips. IP 65 protection for both and optical and electrical compartment. Bottom cover may be with polycarbonate / tempered / toughened glass. Luminaire efficiency should be >60% and ambient temperature >35 deg C. High intensity discharge Electro magnetic ballast with copper winding of Octocyclic winding coil. Class H insulated dual coated copper wire. Compliance to IEC 61347-2-9 Safety and IEC 60923-performance. Winding temperature for HID ballast tw = 130 deg C and temperature rise ?T - 70 deg C. Luminaire shall be suitable to operate on 230/250 Volts 50Hz AC supply finish including wiring, ignitor,condensor. SS toggles for opening front hingeable glass, prewir ed to terminal	Each	8.00	10930.00	Rupees ten thousand nine hundred and thirty only
163	KSRB 4-4.1 : Extra for use of water proofing compound in Cement concrete of mix M25,at one kg of compound per bag of cement. Specification No. KBS (P W D BCSR. 2014-15, P-14, I-4.24)	Cum	14.45	287.00	Rupees two hundred and eighty seven only
164	KSRB 15.3.3Providing 12mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(P W D BCSR. 2014-15, P-109, I-15.11)	Sqm	40.32	149.00	Rupees one hundred and forty nine only

Executive Engineer-2
Lakes, BBMP

Contractor

Scanned by CamScanner

Item Code	Description	Unit	Approved Quantity	Approved Rate in Figures (in Rs.)	Rate in Words (in Rupees)
165	KSRB15-4.1 Extra for providing and mixing waterproofing compound in cement plaster work at one kg per bag or in the proportion recommended by the manufacturers, for cement mortar 1:3, 12mm thick cost of materials complete as per specifications. (P W D BCSR. 2014-15,P-110, I-15.23)	Sqm	70.20	10.00	Rupees ten only
166	KSRB 12-6.3 : Providing cast iron footrest and fixing in manhole with M 10 cement concrete block of 20x20x10cms, using 20mm and down size metal of size including cost of materials, labour charges, curing complete as per specifications. Specification No. KBS 12.4.6 (P W D BCSR. 2014-15 P-70, I-11.46)	nos	15.00	245.00	Rupees two hundred and forty five only
167	Manhole cover PWD BCSR 2012-13 P-XXXVIII, 18" x 24" 38kg	nos	3.00	2136.00	Rupees two thousand one hundred and thirty six only
168	KSRB13-3.4: Providing and fixing in trenches galvanised / mild steel tubes (medium grade) 32mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No.KBS 13.2.14 / 13.6 (P W D BCSR. 2014-15 P-87, I-13.13)	mtr	5.00	336.00	Rupees three hundred and thirty six only
169	KSRB13-4.1 : Making connection of G.I distribution branch with G.I main of 25 to 40mm. nominal bore, including cutting and threading the pipes, providing and fixing Tee, nuts, labour for all item of works, testing and HOM of equipments complete as per specifications. Specification No.KBS 13.10 (P W D BCSR. 2014-15,P-88, I-13.20)	nos	1.00	373.00	Rupees three hundred,and seventy three only
170	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete. (P W D BCSR. 2014-15, P-92, I-13.81.1)	Each	1.00	140.00	Rupees one hundred and forty only
171	Supply and delivery at site brand new MONOBLOCK type-MB series single phase motor suguna / innoval / Lubi / Sabar / Atlanta / Calamal / make suitable for sump tankg to suitable HP suitable speed for operation of 3HP/2.2KW AC supply fitted with required accessories such as suction, Non-Return valve etc., complete. (P W D BCSR 2014-15, P-XXXXV I-1.)	unit	1.00	22366.00	Rupees twenty two thousand three hundred and sixty six only
172	Supply push button operated direct online starter with an antiweld silver cadmium oxide contactor with replaceable fixed and moving contacts and bimetallic thermal overload relay help in anticorrosion treated sheet steel or iron clad enclosure and fixing the same to suitable capacity wires for 400/440 volts 3 phase motor/single phase motor upto 5 HP. (P W D ESR 2014-15, P-44, I-6.1.)	Each	1.00	1513.00	Rupees one thousand five hundred and thirteen only

Executive Engineer-2
Lakes, BBMP

Scanned by CamScanner

Item Code	Description	Unit	Approved Quantity	Approved Rate in Figures (in Rs.)	Rate in Words (in Rupees)
173	Supplying and fixing polished wood board made of not less than 15mm thick plank on both sides of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs srews 20" X 20" X 2.5" (P W D ESR 2014-15, P-44 I-6.6.6)	each	1.00	323.00	Rupees three hundred and twenty three only
174	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers. 100Amps (P W D ESR 2014-15, P-45 I-6.7.1)	each	3.00	127.00	Rupees one hundred and twenty seven only
175	KSRB 5.4-3:Providing and constructing granite / trap / basalt SSM in superstructure with CM 1:4, edges of stones are chistle dressed in courses not less than 15 cms high, bond stones at 2 m apart in each course including cost of all materials, labour,curing complete as per Specifications No. KBS 5.1.13. (P W D BCSR 2014-15 P-23, I-5.12)	cum	8.06	4950.00	Rupees four thousand nine hundred and fifty only
176	KSRB 5-6 : Extra for constructing stone masonry in square or rectangular pillars complete as per specifications. (P W D BCSR 2014-15 P-24, I-5.15)	cum	50.94	290.00	Rupees two hundred and ninety only
177	KSRB 5-8.3 : Providing three line dressing to granite stone slab as per specifications (P W D BCSR 2014-15 P-24, I-5.19)	sqm	228.50	1200.00	Rupees one thousand two hundred only
178	KSRB 5-9 : Providing chamfering edges to granite stone slab 2.5cms. Wide as per specifications (only chamfered length shall be recorded) (P W D BCSR 2014-15 P- 24, I-5.22)	mtr	64.00	34.00	Rupees thirty four only
179	Fabricating, providing and erecting in poiston of Hot dip galvanised M.S.Ornamental security Grill Gate using 75 x 12mm M S Flat for alround frame work with verticals at the centre and horizontal centere support M S Square of 20 x20 mm of different heights as shown in the drawing are to be fixed at 16 cms C/C for suqare bars of full height and at 8cms C / C for bottom rods providg ornamental C I Designers at the botom and C I arrows in the middle and top. The entire frame work is to be fixed by means of expansion bolts to the brick pillars with necesary drillling holes. the work includes providng two coats of enamel painting over one coat of red lead ready mix primer coat etc complete cost of all labour, painting, erection charges using hoist pulleycranes etc as per specification and drawings. (P W D BCSR 2014-15 P-46, I-7.32) 50 kg/sqm	kgs	960.00	179.00	Rupees one hundred and seventy nine only
180	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not less than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. (P W D BCSR. 2014-15,P-25, I-5.27)	sqm	54.00	1034.00	Rupees one thousand thirty four only

Executive Engineer-2
Lakes, BBMP

Scanned by CamScanner

Item Code	Description	Unit	Approved Quantity	Approved Rate in Figures (in Rs.)	Rate in Words (in Rupees)
181	KSRB 5.4-4:Providing and constructing granite / trap / basalt SSM in superstructure with CM 1:4, edges of stones are chistle dressed in courses not less than 15 cms high, bond stones at 2 m apart in each course including cost of all materials, labour,curing complete as per Specifications No. KBS 5.1.13. (P W D BCSR 2014-15 P-23, I-5.13) KSRB 5-5 : Extra lift charges for size stone masonry above ground floor for every additional floor. As directed by the engineer in charge	cum	10.72	5500.00	Rupees five thousand five hundred only
182	Providing and layinglfixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification.As directed by the engineer in charge	Sqm	312.50	1149.00	Rupees one thousand one hundred and forty nine only

Contractor

Executive Engineer-2
Lakes, BBMP

Scanned by CamScanner